



किरोड़ीमल कॉलेज

दिल्ली विश्वविद्यालय, दिल्ली-११०००७

KIRORI MAL COLLEGE

University of Delhi, Delhi-110007

NAAC Accredited A++ 3.54 CGPA, CYCLE 2 NIRF RANK 9 Date:08.04.2026

Sealed percentage rate quotations are invited from the contractors of appropriate class registered with CPWD, M.E.S, Railways or working contractors of University of Delhi for the work "Provision of gutter and pipes for rain water drainage for roofing in Library building at Kirori Mal College University of Delhi." so as to reach the college office by 4.00 p.m. on 20.4.2026.

S. No.	Description of Items	Qty	Unit	Rate
1	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	1	kg	194.40
2	Providing and fixing expansion hold fasteners on C.C. /R.C.C./Brick masonry surface backing including drilling necessary holes and the cost of bolt etc complete. Wedge expansion type Fastener with threaded dia 6 mm	1	Each	36.75
3	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On steel work	1	sqm	241.75
4	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube chollies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding.	1	sqm	338.25
5	Providing and fixing M.S. holder bat clamps of approved design to C.I. or S.C.I. rain water pipes embedded in and including cement concrete blocks 10x10x10 cm of 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) and cost of cutting holes and making good the walls etc. : 150 mm diameter	1	Each	395.60
6	Providing and fixing of Pre-coated colour or mill finish Aluminium Roofing Accessories in 0.71 mm thickness, Alloy 31500 (IS designation) [Aluminium Alloy (AA) 3004 (ISO designation)]. For colour, coating shall be 5-7 microns epoxy primer on both sides of the sheet and polyester top coat 15-18 microns, using self drilling/tapping SS screws of size 6 x 50 mm with 3 mm thick EPDM seal and SS plain washer complete			
6a	Precoated/mill finish aluminium Crimp curve	1	Metre	914.70
6b	Precoated/mill finish aluminium Gutter (600 mm over all girth) including making holes for pipes etc wherever required	1	Metre	1808.65
7	P/F PVC rain water pipe of approved brand and mfg (Astal or equivalent) with clamps etc complete (pressure not less than 6Kg/cm ²) 150 mm nominal dia pipes	1	metre	1500.00
8	Providing and fixing on wall face unplastised - PVC moulded fittings/ accessories for unplastised Rigid PVC rain water pipes (Astal or equivalent) 150 mm bend/ offset etc	1	each	800.00

Conditions:

1. The work should be completed in 60 days
2. 1% water/electricity charges will be recovered.
3. CPWD Specifications will be followed rigidly.
4. The bidder must visit the site of proposed work before submitting the bid.
5. Rates should be quoted both in words & figures.
6. Security @ 5% of the work done will be deducted from the contractor's bill which will be refunded after the defect liability period of one year.
7. Any other extra item or deviation other than the items of work order if required at site during the execution of work will be paid in accordance with the CPWD DSR-2023 or prevailing market rates as applicable with prior approval of competent authority.
8. Undersigned reserves the authority to reject any or all the quotations without assigning any reason thereof.

I/we hereby quote my/our rate as _____% above/below of the estimated rates.


Principal