



किरोड़ी मल कॉलेज

दिल्ली विश्वविद्यालय, दिल्ली-११०००७

KIRORI MAL COLLEGE

University of Delhi, Delhi-110007


Date: 02.02.2026

Sealed quotations are invited from the contractors of appropriate class registered with CPWD, M.E.S, Railways or working contractors of University of Delhi for the work "Repair of waterproofing on roof of Boys common room at Kirori Mal College, University of Delhi." so as to reach the college office by 4.00 p.m. on 12.02.2026.

S. No	Description of Items	Unit	Qty	Rate	Amount
1	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement: 3 fine sand) as per standard design: In 75x75 mm deep chase	mtr	10	305.15	3051.50
2	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement: 4 fine sand)	sqm	5	547.4	2737.00
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer 3 mm thick water proofing membrane, black finished reinforced with non-woven polyester matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/sqm by the same membrane manufacture of density at 25°C, 0.87-0.89 kg/ litre and viscosity 70-160 cps. Over the primer coat the layer of membrane shall be laid using Butane Torch and sealing all joints etc, and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under: Joint strength in longitudinal and transverse direction at 23°C as 650/ 450N/ 5cm. Tear strength in longitudinal and transverse direction as 300/250N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D - 5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane: 3 mm thick	sqm	300	560.95	168285.00
4	Grading roof for water proofing treatment with Cement mortar 1:4 (1cement: 4 coarse sand)	cum	1	15155.6	15155.60
				Total	1,89,229.10

Conditions:

1. The work is to be completed in 30 days.
2. 1% water/electricity charges will be recovered.
3. CPWD Specifications will be followed rigidly.
4. Rates should be quoted both in words & figures.
5. Undersigned reserves the authority to reject any or all the quotations without assigning any reason thereof.


Principal

I/we hereby quote my/our rate as _____% above/below of the estimated rates.

Agency